BOQ for Landscape development work in Engg. Extension at Mahindra World City, Jaipur

Tender No. MWCJL/INFRA/SEZ/LANDSCAPE WORKS/2019-20/T-008

S.NO.	Description of Items	Unit	Qty	Rate	Amount
1	Top Soil - Preparation - filling of soft soil upto 150mm with required excavation and transportation of soil within 2 KM and soil preparation for shrub should include 25 -50 mm thick layer of decompose farmyard manure mixed thoroughly with Sulphur, gypsum, reagent or any other required additives including excavation, filling, transportation, etc.as per direction of Engineer-in-Charge.	cum	5,247		
2	Supply, Spreading sledge/manure Spreading of 50mm thick decompose farmyard manure on planting bed prior to mixing with soil.	cum	1,749		
3	Supply and Applying Fertilizer 50 gm/sqm (NPK / DAP).	kg	1,749		
4	Shrubs Supply, plantation & Maintenance				
а	Tecoma stans	sqm	3,180		
b	BOUGAINVILLEA SPECTABILIS RED 0.6m O.H @0.6m SPC	sqm	992		
С	Cascabela thevetia	sqm	1,140		
d	CARRISSA CARANDUS	sqm	1,089		
е	Enermy	sqm	1,455		
f	NERIUM OLEANDER RED 0.6m O.H @0.6m SPC	sqm	2,726		
	Total Basic Price				
	GST @ 18%		-		
	Grand Total				
	Grand Total in Lacs				

Note:-

- 1. Rate should be inclusive of cost towards all statutory, compliances, all charges ,etc except GST which shall be extra as applicable.
- 2. Rate should be inclusive of free maintenance period of 12 months, for which contractor shall be paid 60% amount after actual completion and 40% amount shall be paid in four installments (Quarterly).
- 3. Part Payment /R.A. Bill upto maximum of 60% of total contract value can be released as per proposal by Engineer-in-Charge
- 4. Any extra Items /increase in qtys. other than BOQ shall be pre-intimated before execution. Such Items shall be recoded in Site Instruction book and same shall be paid in final RA bill as per approval by Engineer-in Charge based on proper rate analysis (in case of extra items) by Contracts Deptt.