

MAHINDRA WORLD CITY , JAIPUR					
BOQ FOR INTERNAL AND EXTERNAL PAINTING WORKS IN SEZ MP AND DTA ZONE.					
Tender No. MWCJL/O&M/SEZ & DTA/PAINTING/2020-21/T-005 DT. 31.12.2020					
S.No.	Description	Unit	Qty.	Rate (Rs)	Amount
(A)	<u>Evolve. (MP SEZ)</u>				
1	Internal Paint: Providing and applying two or more coat of Acrylic Emulsion paint on internal walls. (Make -Berger/ Asian/ICI) incl. preparation of surface and shade on existing surface only as per direction of Engineer-in-Charge if required.	Sqmtr	7900		
2	Internal Paint: Providing and applying two or more coat of Plastic paint on internal walls. (Make -Berger/ Asian/ICI) incl. preparation of surface and shade on existing surface only as per direction of Engineer-in-Charge if required.	Sqmtr	1100		
TOTAL (A)			9000		-
(B)	<u>MP SEZ</u>				
1	Internal Paint: Providing and applying two or more coat of Acrylic Emulsion paint on internal walls. (Make -Berger/ Asian/ICI) incl. preparation of surface and shade on existing surface only as per direction of Engineer-in-Charge.	Sqmtr	5990		
2	External Paint: Providing and applying two or more coats of exterior grade texture paint on wall surfaces (Make -Berger/ Asian/ICI) including surface preparation, scaffolding etc complete as per manufacturers specificaton and top surface finished as per requirement of MWCJ Engg.	Sqmtr	2825		
TOTAL (B)			8815		-
(C)	<u>DTA</u>				
1	Internal Paint: Providing and applying two or more coat of Acrylic Emulsion paint on internal walls. (Make -Berger/ Asian/ICI) incl. preparation of surface and shade on existing surface only as per direction of Engineer-in-Charge.	Sqmtr	3730		
2	External Paint: Providing and applying two or more coats of exterior grade texture paint on wall surfaces including surface preparation, scaffolding etc complete as per manufacturers specificaton and top surface finished as per requirement of MWCJ Engg.	Sqmtr	2105		
TOTAL (C)			5835		-
TOTAL (A+B+C)			23650		-
GST 18%					-
GRAND TOTAL					-
Note:- 1. Rate is inclusive of cess,all charges ,labour charges except GST. (GST nil in MP SEZ against LUT) 2. Time is essence of the Contract. Work to be completed within 60 days. 3. Any extra Items /increase in qtys. other than BOQ shall be pre-intimated before execution. Such Items shall be recorded in Site Instruction book and same shall be paid as per approval by Engineer-in Charge based on proper rate analysis (in case of extra items) by Contracts Deptt and the same shall be paid in final invoice.					