

MAHINDRA WORLD CITY , JAIPUR					
BOQ FOR EXCAVATION AND BACKFILLING (DTA-II)					
S. No.	Description of items	Unit	Quantity	Rates (Rs.)	Amount
1	Excavation works				
1.1	Earth work in excavation by mechanical means (Hydraulic excavator) including disposal of excavated earth, lead upto 1.5KM and lift upto 2.5m, including the cost of removing shrubs, logs, roots, jungles if any, disposed earth to be levelled and neatly dressed/ compacted including transporting to the plot shown by the Engineer in charge. The quoted rate shall include the cost of watering, compacting, and consolidating the surface using by vibratory roller 8 to 10 T capacity to achieve maximum laboratory dry density (IS:2720 Part-8) with optimum moisture content etc to the satisfaction of engineer in-charge. (Payment shall be made for the finished item of work after compaction based on original and finished levels). The quoted rate shall include the disposal of excavated soil within the radius of 1.5 KM from work area as per direction of engineer-in-charge.	CUM	25,000.00		0.00
	Total Amount For Service (Rs.)				-
	CGST on Services @ 9%				-
	SGST on Services @ 9%				-
	Total Amount with tax (Rs.)				-
Note:-					
1	Rate should be inclusive of cess,all charges ,labour charges except GST, which shall be paid extra as applicable.				
2	Time is essence of the Contract. Work to be completed within 15 days.				
3	Any extra Items /increase in qtys. other than BOQ shall be pre-intimated before execution. Such Items shall be recorded in Site Instruction book.				