

GENERAL NOTES:

(1) This drawing is the property of Mahindra Consulting Engineers Ltd,(MACE) Chennai India and must not be passed on to any body not authorized by MACE neither to receive it nor to be copied or otherwise made use of either in full or in part by such person or body without the prior permission in writing. This drawing cannot be handed over to a third party or used for any purpose, other than that for which it has been intended.

(2) Do not scale from the drawing.

(3) All dimensions are in millimeters and levels are meters unless noted otherwise. All dimensions to be verified on site & approved by the engineer.

LEGEND:

- 150 mm Ø Sewer main RCC pipe
- 200 mm Ø Sewer main RCC pipe
- 250 mm Ø Sewer main RCC pipe
- 300 mm Ø Sewer main RCC pipe
- Manhole

NOTE:

NP3 RCC pipe with sulphate resistant cement.

SCHEDULE OF QUANTITY

100 mm Ø	-	662 M (RCC)
150 mm Ø	-	158 M (RCC)
200 mm Ø	-	2282 M (RCC)
Manhole	-	79 Nos

NOTE:

CONSIDER PLOT MANHOLE ONLY IN PHASE-II AND MAIN MANHOLES CONSIDERED IN PHASE-I FOR 64 M WIDE CENTRAL SPINE ROAD.

Good for construction

Rev	Description	Date
GFC	Good for construction	27.10.2017
R2	MWCJL comments incorporated	25.07.2017
R1	Relocated the STP	09.03.2017

CLIENT :

Mahindra World City Jaipur limited.

PROJECT CONSULTANT :

Mahindra Consulting Engineers

TEL:044-28542325,28542326
FAX:044-28542324
e-mail:mace@mahindra.com
Website:www.mahindramace.com

Mahindra Towers.
Ground Floor, No.17/18,
Pattullous Road,
Chennai-600 002.

PROJECT TITLE :

Mahindra World City - Jaipur
DTA - II

DWG. TITLE :

Sewerage network - Phase II

Scale:	Size:	Date:	Sheet:
1:2500	A1	05.01.2017	1 of 2

Job No.:	Drawing No.:	Rev:
MACE-946	MWCJ/SEWER/02	GFC